

Stennis Space Center Policies & Procedures

The following clauses, policies and procedures apply only to work performed at Stennis Space Center (SSC), Mississippi:

1. Definitions

Paragraph 1. Definitions, of the attached SM353, Additional Provisions For Work Performed At A Government Installation (Site)(SPOC), shall apply to the clauses below.

2. Asbestos Material

(a) During performance of this contract, Contractor and subcontractor personnel performing work in SSC buildings may come in contact with materials containing asbestos. Portions of SSC buildings 1000, 1100, 1105, 1200, 2101, and 2201 contain asbestos spray-applied insulation. Other buildings may contain asbestos around pipes, valves, ducts, boilers, and tanks. The Contractor shall be responsible for ensuring all applicable codes, standards and regulations are adhered to and enforced, including OSHA Standard 29 CFR 1910.1001, OSHA Standard 29 CFR 1926.58, and USEPA 40 CFR 61, Subpart M. Prior to disturbing this material in any manner, the Contractor shall notify the NASA Environmental Office for guidance. The Contractor shall be responsible for ensuring all Contractor and subcontractor personnel are made aware of and comply with this clause.

(b) SSC has an Asbestos Abatement Plan which addresses procedures for work involving potential asbestos exposure. The Contractor will be required to comply with the provisions of this plan whenever its work involves the potential for exposure to asbestos. Reference SSC Asbestos Management and Abatement Program Plan dated August 17, 1992.

3. Hazardous Material And Hazardous Waste Management

During the performance of this contract, the Contractor or subcontractors may be required to requisition, handle and manage hazardous materials in support of specific projects. The Contractor may also be collecting waste generated by its activities for ultimate disposal by NASA. In the performance of these activities, the Contractor shall abide by the most recent version of SMI 4130.1, Control of Hazardous Materials, SHB 4130.2, Hazardous Materials, Hazardous Waste and Solid Waste Management Plan, the SSC Contingency Plan for Response to Spills of Oil and Hazardous Substances, and the SSC Spill Prevention Control and Countermeasures Plan.

4. Environmental Planning

During the performance of this contract, the Contractor or subcontractors may be required to design projects or perform projects that will potentially impact the environment. To guide the Contractor in what needs to be considered in project designs and planning, the Contractor shall reference the SSC Environment Resources Document (ERD). The development and submission to the NASA Environmental Office of the Preliminary Environmental Survey found in the ERD is required if there is any potential impact to the environment in the project. The NASA Environmental Office will determine if the project will require evaluation under the National Environmental Policy Act and what environmental permits will be needed prior to proceeding with the project.

